

Safety, Health and Environment Information.
Notes below are additional to hazard/risks normally associated with this type of work:

Construction
Ci. Site team to agree speed reduction to 30mph with local authority.
Cii. Tree clearance to be agreed with local authority and land owner.
Ciii. Site team to liaise with BT to confirm excavation around their service is ducted.
Civ. Site team to monitor performance of culvert and ensure it is kept clear of debris. No hydraulic calculations have been undertaken for this culvert.




Operations
Oi.
Maintenance
Mi.
Dismantling/Demolition (future)
Di.

These notes are based on the use of experienced and competent contractors carrying out the work using an approved safe method of working.
The Temporary Works Coordinator (or other suitably competent person) is responsible for the implementation of these works on site and notifying the designer of any changes.

Save as is permitted by the terms for the provision of this document, copyright in this document belongs to Kier Professional Services Limited. It is a condition of the supply of this document that the recipient shall not duplicate or reproduce it in whole or in part, nor disclose its contents without the written authorisation of Kier Professional Services Limited. No liability shall be accepted for its unauthorised use.

Notes:

- Unless shown otherwise or indicated in the Specification, whichever is the more onerous, dimensional tolerance is to be in accordance with Tables 1 and 2 of BS 5606.
- All dimensions are in millimetres (mm) unless noted otherwise. **DO NOT SCALE FROM THIS DRAWING, USE FIGURED DIMENSIONS ONLY.**
- This drawing is to be read in conjunction with the Specification and any Specialist drawings.
- Refer also to:
Schedule numbers:
Drawing numbers:
- UNLESS THE REVISION OF THIS DRAWING IS DENOTED BY THE PREFIX C THEN THIS DRAWING IS NOT FOR CONSTRUCTION.
- Slab designed for normal highway loads and 30T dumpers. Design to be consulted over any abnormal loads
IF IN DOUBT ASK



SETTING OUT POINTS		
POINT NUMBER	EASTING	NORTHING
SOP 1	394371.852	86358.899
SOP 2	394379.350	86362.534
SOP 3	394384.899	86371.841
SOP 4	394397.945	86371.841
SOP 5	394395.915	86363.578
SOP 6	394382.331	86359.254

WORK IN PROGRESS

P01	09/01/23	First issue.	JRB	SH	OP
Issue	Date	Description	Drawn	Des.	Chkd.
Issue codes:- F: Feasibility T: Tender P: Preliminary C: Construction AB: As built					
Drawing status: NOT FOR CONSTRUCTION					
<p>Kier Professional Services Limited 160 Aztec West, Bristol, BS32 4TU.</p> <p>www.kier.co.uk professional.services@kier.co.uk</p>					
Client: REGIONAL CIVILS					
Contract: ARNES MOORS					
Title: SITE ACCESS GA					
Scale (A1): As Shown			Drawing No. 56-21009-DR-0001 Issue P 01		

100 on Original - A1

100 on Original - A1

Plotted by: mak, mike 20/01/2023 12:27:57 File reference: 56-21009-DR-0001 to 03_Site Access GA.dwg